



तिनाउ गाउँपालिका
Tinau Rural Municipality

गाउँ कार्यपालिकाको कार्यालय
Office Of The Rural Municipal Executive

पत्र संख्या /Letter No.:- ०५१/०८५
चलानी नं /Ref. No.:- १६७

दोभान, पाल्पा
Dobhan, Palpa
स्था : २०७३ / Estd. २०१७ A.D.

लुम्बिनी प्रदेश, नेपाल
Lumbini Province, Nepal

दररेट पेश गर्ने सम्बन्धी सुचना

प्रथम पटक प्रकाशित मिति २०८१।०७।११

१.तिनाउ गाउँपालिकाद्वारा विभिन्न निर्माण व्यवसायी संग तपिशल बमोजिमको कार्य गर्न दररेट पेश गर्नका लागि यो सुचना प्रकाशित गरिएको छ ।

तपिशल

क्र.स.	कार्य विवरण	जम्मा रकम (मुल्य अभिवृद्धि कर ,भ्याट सहित) कन्टेन्जेन्सी बाहेक	दररेट पेश गर्ने अन्तिम मिति	कै.
१	वार्ड-०१ पहिरो सफाई गर्ने कार्य	५,५५,८४५.७७/-	२०८१।०१।२५	

२. दररेट पेश गर्ने निर्माण व्यवसायीले अनिवार्य रूपमा दररेट पेश गर्ने ब्यहोरा सम्बन्धमा लिखित निवेदन सहित नविकरण भएको फर्म/ कम्पनी दर्ता प्रमाणपत्रको प्रतिलिपी,नविकरण भएको व्यवसाय दर्ता (निर्माण व्यवसायी इजाजत प्रमाण पत्र) प्रमाणपत्रको प्रतिलिपी,मु.अ.क.दर्ता प्रमाणपत्रको प्रतिलिपी र आर्थिक वर्ष २०७९/८० को करचुक्ता प्रमाणपत्रको प्रतिलिपी र म्याद थप संलग्न गरि पेश गर्नुपर्नेछ ।

३. BOQ, Specification यस कार्यालयको Webside बाट समेत डाउनलोड गर्न सकिनेछ ।

४.दररेट पेश गर्ने निर्माण व्यवसायीले कार्यालयमा अनिवार्य सुचिकृत गर्नुपर्नेछ । सुचिकृत नभएका निर्माण व्यवसायीलाई मुल्याङ्कनमा समावेश गर्न सकिने छैन ।



लेख बहादुर बस्नेत

प्रमुख प्रशासकीय अधिकृत

प्रमुख प्रशासकीय अधिकृत

Tinai Rural Municipality
Office of Municipal Executive
Dobhan -02, Lumbini Province
Palpa, Nepal
Bill of Quantity

प्रमुख प्रशासकिय अधिकृत

Project: Landslide clearance on Ward no 1

F.Y: 2081/082

Location: Tinai 1,2

S.N.	Item Name & Description of Work	Unit	Qty	Rate in Figure NRS	Rate in Words	Amount (Rs.)	Remarks
A	Civil Works						
1	Clearance Of Land Slides on mix type of Soil And Ordinary Rock By Machine And Disposal Of The Same volume On The Valley Side as per instruction of site incharge .	Cum	2078.66				
2	Site Clearance For Road and small size reels maintenance on road to make servicable condition as per instruction of site incharge (Mechanical Means)	Sqm	4213.10				
3	Maintenance Of Earthen Shoulder (Filling With Fresh Soil) Providing And Making Up Loss Of Material/ Irregularities On Shoulder To The Design Level By Adding Fresh Approved Soil And Compacting As Per Technical Specification And as per instruction of site incharge.	Sqm	3548.60				
4	Providing And Laying Of River bed mixed type of soil to make motarable road as per instruction of site incharge.	Cum	108.00				
5	Mechanically Roadway and Drain excavation in all types of soil as per Drawing and Technical Specification including removal of stumps and other deleterious matter, all lift and leads as per Drawing and Instruction of the Engineer.	Cum	252.00				
6	Laying Local Gravel as per instruction of site incharge.	Cum	150.00				
Total Cost for all Item							
VAT @ 13 %							
Grand Total (A)+(B)							

The total price of our Bid, excluding any discounts offered is :

Name of Bidder/Suppliers
Address

Bidder's /Suppliers Legal Name

Bidder's /Suppliers Address:

Bidder/Suppliers Country of Registration:

Bidder/Suppliers Year of Registration:

Bidder/Suppliers Authorized Representative Information:

Name: _____ Address: _____
Telephone/Fax numbers: _____ Email _____

Address

We have examined and have no reservations for this Supply of Goods.

We offer to supply in conformity with the delivery schedule as per office Requirements

Official Stamp