



तिनाउ गाउँपालिका
Tinau Rural Municipality

गाउँ कार्यपालिकाको कार्यालय
Office Of The Rural Municipal Executive

पत्र संख्या /Letter No.:-
चलानी नं /Ref. No.:-

दोभान, पाल्पा
Dobhan, Palpa
२०७३ / वि.सं. २०१७ A.D.

लुम्बिनी प्रदेश, नेपाल
Lumbini Province, Nepal

दररेट पेश गर्ने प्रतिस्पर्धी सूचना

प्रथम पटक प्रकाशित मिति २०८१।१०।३०

१. तिनाउ गाउँपालिकाद्वारा विभिन्न निर्माण व्यवसायी संग तपशिल बमोजिमको कार्य गर्न दररेट पेश गर्नका लागि यो सूचना प्रकाशित गरिइएको छ ।

तपशिल

क्र. स.	कार्य विवरण	जम्मा रकम (मुल्य अभिवृद्धि कर, भ्याट सहित) कन्टेन्जेन्सी बाहेक	दररेट पेश गर्ने अन्तिम मिति	कै.
१	सिचाई योजना खा.पा प्रभावित क्षेत्र तिनाउ गा.पा. ३, पाल्पा	७,८२,२८४.९८	२०८१।११।०६ अफिस समय भित्र	

२. दररेट पेश गर्ने निर्माण व्यवसायीले अनिवार्य रूपमा दररेट पेश गर्ने ब्यहोरा सम्बन्धमा लिखित निवेदन सहित नविकरण भएको फर्म/ कम्पनी दर्ता प्रमाणपत्रको प्रतिलिपी, नविकरण भएको व्यवसाय दर्ता (निर्माण व्यवसायी इजाजत प्रमाण पत्र) प्रमाणपत्रको प्रतिलिपी, मु.अ.क. दर्ता प्रमाणपत्रको प्रतिलिपी र आर्थिक वर्ष २०८०/८१ को करचुक्ता प्रमाणपत्रको प्रतिलिपी संलग्न गरि पेश गर्नुपर्नेछ ।

३. BOQ, Specification यस कार्यालयको Webside बाट समेत डाउनलोड गर्न सकिनेछ ।

४. दररेटपेश गर्ने निर्माण व्यवसायीले कार्यालयमा अनिवार्य सुचिकृत गर्नुपर्नेछ । सुचिकृत नभएका निर्माण व्यवसायीलाई मुल्याङ्कनमा समावेश गर्न सकिने छैन ।

लेखबहादुर बस्नेत
प्रमुख प्रशासकीय अधिकृत
प्रमुख प्रशासकीय अधिकृत

Tinau Rural Municipality
Office of Municipal Executive
Dobhan -02, Lumbini Province



Nepal
Municipality

तिनाउ गाउँपालिका
सुदूरपश्चिम प्रदेश

कार्यक्रम/योजनाको नाम: सिचाई योजना खा. पा. प्रभावित क्षेत्र तिनाउ गा.पा. ३, पाल्पा
कार्यक्रम / योजनाको नाम र कार्यान्वयन हेतु स्थल: तिनाउ गाउँपालिका - ३, पाल्पा

F.Y. 2081/082

S.N.	Item Name & Description of Work	Unit	Rate in Figure NRS	Rate in Words	Amount (Rs.)	Remarks
Provisional Sum						
1	Supply and fixing of one contract information board (hoarding board) 3'x4' size as per direction. Additional Lab test and reports as per instruction of Engineers all complete.	Ps	1.00			
Civil Works						
1	MANUAL EARTH WORK IN EXCAVATION: Excavation in foundations For Drain and Structure in all type of soils for foundation, trenches, footing, pits etc. to the required depth including lift up to 2.5m timbering, dewatering by manual or mechanical means etc. as per specifications with all contractor's own machinery and equipments, providing crossing of track, shoring, strutting, timbering and buttressing with appropriate materials and all such measures necessary to retain, in position the sides of the foundation pit and including refilling the excavated material with watering, ramming, leveling the site and disposing off the surplus/unusable earth to outside the construction premises up to a lead of 30m, etc. all complete as per drawings, specifications and instructions of the Engineer.	Cum.	45.41			
2	Providing and laying of hand pack Stone soiling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface of Canal Bed and Hydraulic Structures as per Drawing and Technical Specifications.	Cum.	17.21			
3	Providing and laying of PCC (Grade M 15) in Canal Bed and Hydraulic Structures complete as per Drawing and Technical Specifications (As per 20-01, SS 2000)	Cum.	30.85			
4	Providing and laying of RCC (Grade M 20) in Canal Bed and Hydraulic Structures complete as per Drawing and Technical Specifications. (As per 20-02 C, SS 2000)	Cum.	3.77			
5	STONE MASONRY WORKS: Providing and laying Rubble Stone Masonry works in cement mortar 1:4 (1 cement : 4 coarse sand) in all level and heights of Good quality stone in perfect line level finish including cleaning the stone, cutting in perfect shape and finishing, retaining wall and pathway etc. including the cost of scaffolding, breaking stones, raking joints, curing, all complete as per drawing, specifications and instructions of the Site Incharge.	Cum.	5.25			

Tinau Rural Municipality
Office of Municipal Executive
Dobhan -02, Lumbini Province

Palpa Nepal
Bill of Quantity



कार्यक्रम/योजनाको नाम: सिचाई योजना खा.चा प्रभावित क्षेत्र तिनार गा.पा. ३, चाल्वा
कार्यक्रम / योजनाको नाम र कार्यस्थल हने स्थल: तिनार गाउँपालिका - ३, चाल्वा

F Y 2081 / 082

S.N.	Item Name & Description of Work	Unit	Qty	Rate in Figure NRS	Rate in Words	Amount (Rs.)	Remarks
6	Providing and laying, fitting and placing HYSD bar reinforcement in foundation complete as per Drawing and Technical Specifications (As per 20.05, SS Clause 2014)	kg	225.79				
7	Supplying, Laying and fitting of 110 mm diameter PN10 HDPE pipe (PE100, NS40) all complete]	Rm	10.00				
8	Gabion work: Supplying of heavy zinc coated machine made All size gabion boxes, hexagonal mesh size 100x120 mm, mattress/boxes with diaphragms with lacing wire 2.4mm, mesh wire 3mm and salvage wire 3.9mm assembling gabion boxes mattress placing in position including stretching forming compartment tying with bracing wire and tie wire tying down the lid complete and providing and filling stone/boulder in gabion boxes mattress etc. including dressing bedding, bonding, transportation all complete as per specification.	Cum.	8.00				
Total Cost for all Item							
VAT @ 13 %							
Grand Total (A)+(B)							

The total price of our Bid, excluding any discounts offered is :

Name of Bidder/Suppliers

Address

Bidder's /Suppliers Legal Name

Bidder's /Suppliers Address:

Bidder/Suppliers Country of Registration:

Bidder/Suppliers Year of Registration:

Bidder/Suppliers Authorized Representative Information:

Name:

Address:

Telephone/Fax numbers:

Email

Address

We have examined and have no reservations for this Supply of Goods

We offer to supply in conformity with the delivery schedule as per office Requirements

Official Stamp