



तिनाउ गाउँपालिका  
Tinau Rural Municipality  
गाउँ कार्यपालिकाको कार्यालय

Office Of The Rural Municipal Executive

दोभान, पाल्पा  
Dobhan, Palpa

लुम्बिनी प्रदेश, नेपाल  
Lumbini Province, Nepal

प.सं.: २०८२/०८३

च.नं.:

स्थापना: २०१३/Est'd 2017 A.D.


दररेट पेश गर्ने सम्बन्धी सूचना

प्रथम पटक प्रकाशित मिति २०८३/०१/१६

१. तिनाउ गाउँपालिका अन्तर्गत तपसिल बमोजिमको कार्य गर्न सिलबन्दी रूपमा दररेट पेश गर्नका लागि सम्बन्धित फर्म/कम्पनीको जानकारीको लागि यो सूचना प्रकाशित गरिएको छ।

क्र.सं.	कार्य विवरण	जम्मा रकम (मु.अ.कर सहित) कन्टिजेन्ससी बाहेक	दररेट पेश गर्ने अन्तिम मिति	कैफियत
१	रूपा प्राथमिक विद्यालय भवन मर्मत	७,८०,५६१।३१	२०८३/०१/२२	

२. दररेट पेश गर्ने फर्म/कम्पनीले अनिवार्य रूपमा दररेट पेश गर्ने व्यहोरा सम्बन्धमा निवेदन सहित नविकरण भएको फर्म/कम्पनी दर्ता प्रमाणपत्रको प्रतिलिपी, नविकरण भएको व्यवसाय दर्ता(निर्माण व्यवसायी ईजाजत प्रमाण पत्र) प्रमाणपत्रको प्रतिलिपी, मु.अ.कर दर्ता प्रमाणपत्रको प्रतिलिपी र आर्थिक वर्ष ०८१/०८२ को करचुक्ता प्रमाणपत्रको प्रतिलिपी संलग्न गरी पेश गर्नुपर्नेछ।
३. BOQ, Specification यस कार्यालयबाट प्राप्त गर्न सकिनेछ साथै यस कार्यालयको website बाट समेत डाउनलोड गर्न सकिनेछ।
४. दररेट पेश गर्ने निर्माण व्यवसायी कार्यालयमा अनिवार्य सुचिकृत भएको हुनुपर्नेछ। सुचिकृत नभएका निर्माण व्यवसायीलाई मुल्याङ्कनमा समावेश गर्न सकिने छैन।

  
०८१/०८२  
.....  
(दिनेश सारु)  
प्रमुख प्रशासकीय अधिकृत

Website: [www.tinaumun.gov.np](http://www.tinaumun.gov.np)

Contract No.:075-413064/63  
Email: [tinaururalmunicipality@gmail.com](mailto:tinaururalmunicipality@gmail.com)

Tinau Rural Municipality  
Office of Municipal Executive  
Dobhan -02, Lumbini Province  
Palpa Nepal

*[Signature]*  
प्रमुख प्रशासकीय अधिकृत

Bill of Quantity

F.Y: 2082/83

Project : रूपा प्राथमिक विद्यालय भवन मर्मत  
Location : Tinau R.M-02 Nuwakot, Palpa.

Sl. No.	Item Name & Description of Work	Unit	Qty	Rate in Figure NRs	Rate in Words	Amount (Rs.)	Remarks
A	Provisional Sum						
1	Providing and installation of project signboards with size of 1.8 x 1.2 m. Additional Lab test and reports as per instruction of Engineers all all complete.	PS	1	3000.00	Three Thousand Only	3000.00	
B	Civil and Goods						
1	Earth work in excavation in hard ,boulder mixed soil for foundation trench including Timbering and pumping out water from the trenches(if necessary), Ramming of bottom, lift up to 2m lead 10m, stacking of excavated materials , clear from the edge of foundation trench and backfilling after work completion all complete as per specification & instruction of site engineer.	Cum	16.30				
2	EARTH WORK IN BACKFILLING: Earth work in filling by borrowed soil in foundation, floor, building periphery etc. shall be done with good excavated soil in the floor with proper ramming in 20cm layers ,after sprinkling water and consolidating to 15 cm layer including transportation of soil, spreading in required line and level, sprinkling water, ramming, compacting with mechanical rammers, testing, etc.as per drawing, specification and instruction of engineer, all complete.	Cum	19.97				
3	STONE/BOULDER SOLING: Providing and laying 150mm boulder/stone soling in foundation and floor with approved quality stone/boulder in required line and level including filling joints with sand all complete as per drawings, specifications and instructions of the Site Incharge.	Cum	6.02				

**Tinau Rural Municipality**  
**Office of Municipal Executive**  
**Dobhan -02, Lumbini Province**  
**Palpa Nepal**

**Bill of Quantity**

**Project : रूपा प्राथमिक विद्यालय भवन मर्मत**

**Location : Tinau R.M-02 Nuwakot, Palpa.**

F.Y: 2082/83

*[Signature]*  
 पाल्पा प्रशासकीय अधिकारी  
 मिति: २०८२/०३/०३  
 नगरपालिका कार्यालय  
 पाल्पा

S.N	Item Name & Description of Work	Unit	Qty	Rate in Figure NRS	Rate in Words	Amount (Rs.)	Remarks
4	PLAIN CEMENT CONCRETE WORK: Providing and laying machine mixed Plain Cement Concrete of nominal mix 1:2:4 (1 cement : 2 sand : 4 coarse aggregate ) for leveling course in foundations and floor of building, wherever necessary, dewatering, batching, mixing, transporting, placing, compacting, curing, including all lead and lift, etc. all complete as per drawings, specifications and the instructions of the Engineer.	Cum	6.65				
5	Plain cement Concrete (PCC) for RCC works M 20(1:1.5:3) for Beam, Footing, Column and Slab with approved quality of cement, sand and machine crushed stone aggregate including supply of materials, mixing, laying, curing the work at least 7 days etc all complete as per approved drawing, Specification and instruction of site engineer.	Cum.	3.09				
6	TMT steel reinforcement bar of fe 500 grade including supplying, straightening, cleaning, cutting, binding & fixing in position with annealed tying binding wire all complete as per approved drawing. Specification and instruction of site engineer.	KG	139.50				

**Tinau Rural Municipality**  
**Office of Municipal Executive**  
**Dobhan -02, Lumbini Province**  
**Palpa Nepal**  
**Bill of Quantity**

  
**प्रमुख प्रशासकीय अधिकृत**

F.Y: 2082/83

**Project : रूपा प्राथमिक विद्यालय भवन मर्मत**  
**Location : Tinau R.M-02 Nuwakot, Palpa.**

S.N	Item Name & Description of Work	Unit	Qty	Rate in Figure NRS	Rate in Words	Amount (Rs.)	Remarks
7	FORMWORK: Supplying and laying centering, shuttering of various pattern formworks with 19/12 mm thick water proof ply wood & steel adjustable props for all kinds of RCC works for foundations, columns, shear walls, beams, slab, staircase, lintel, sill, pergola, including nails, propping scaffolding, staging, supporting and bracing in proper lines and level, sealing the joints with heavy duty brown self adhesive tape, aligning to line and levels including Ties, PVC Spacer, Providing openings/ cutouts/ pockets, applying deshuttering chemical, deshuttering as approved by the Engineer etc., complete at all levels as per drawing, specifications and instructions of the Engineer.	Sqm	17.04				
8	STONE MASONARY WORK :Providing and constructing in substructure With 1:6 cement Sand mortar of Good quality stone in perfect line level finish including cleaning the stone, cutting in perfect shape and finishing all complete as per instruction and requirement of site.	Cum	7.71				
9	BRICK WORK : Providing and laying, brick work in 1:4CM in foundation and superstructure with approved quality first class brick in perfect line and level, finished including wetting the bricks, packing the joints and curing the work and necessary scaffolding, complete	Cum	8.93				

**Tharu Rural Municipality**  
**Office of Municipal Executive**  
**Dobhan -02, Lumbini Province**  
**Palpa Nepal**  
Bill of Quantity

*[Signature]*  
**प्रमुख प्रशासकीय अधिकारी**  
**पाल्पा**

*[Stamp]*  
**पाल्पा**

F.Y: 2082/83

**Project :** ~~Water supply~~ **Water supply**  
**Location :** **Tharu R.M-02 Nepalgunj, Palpa**

Sl. No.	Particulars	Unit	Qty	Rate in Nepalese Rupee	Rate in Rupee	Amount (Rs.)	Remarks
10	M/S STEEL TUBULAR TRUSS: Supplying and fixing; Steel roof trusses with B.S. or I.S. steel sections including hoisting and fixing with necessary M.S. base plates, shoes, angles, anchor bolts, leadbolting or cement grouting, painting with 2 coat of primer and two coat of enamel paint etc as per drawing, specification and instruction of engineer, all complete.	Kg	351.40				
11	C.G.L SHEET: Roofing with approved Corrugated Galvanised colored iron (C.G.L) sheet of 0.45mm thick on roof including fixing in proper shape and size with necessary nails, screws, bolts and nuts, washers, J or L hooks bolts, etc. as per drawing specification and instruction of site Engineer, all complete.	sq.m	63.00				
12	RIDGE COVER: Providing and laying with approved size of 26 Gauge medium thick colored ridge cover over the ridge of C.G.L. sheet on roof including fixing in proper shape and size with necessary nails, screws, bolts and nuts, washers, J or L hooks bolts, etc. as per drawing specification and instruction of engineer, all complete.	R.m	10.00				
13	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including scaffolding wherever necessary, sorting the dismantled Material, disposal of unserviceable Material and stacking the serviceable Material with all lifts and lead of 1000 meters (By Mechanical Means)- (i,B) Prestressed / reinforced cement concrete grade M-20 & above	Cum	51.75				

**Timau Rural Municipality  
Office of Municipal Executive  
Dobhan -02, Lumbini Province  
Palpa Nepal**

Bill of Quantity

F.Y: 2082/83

**Project : स्या प्राथमिक विद्यालय भवन सर्वात**  
**Location : Timau R.M-02 Nuwakot, Palpa.**

SN	Item Name & Description of Work	Unit	Qty	Rate in Figure NPR	Rate in Words	Amount (Ru)	Remarks
	Total Cost for all Item						
				VAT @ 13 %			
				Grand Total (A+13)			

The total price of our Bid, excluding any discounts offered is

Name of Bidder/Supplier \_\_\_\_\_  
Address \_\_\_\_\_

Bidder's Suppliers Legal Name \_\_\_\_\_  
Bidder's Suppliers Address \_\_\_\_\_

Bidder/Supplier's County of Registration \_\_\_\_\_  
Bidder/Supplier's Year of Registration \_\_\_\_\_

Bidder/Supplier's Authorized Representative Information \_\_\_\_\_  
Address \_\_\_\_\_

Email Address \_\_\_\_\_ Telephone Name \_\_\_\_\_  
Name \_\_\_\_\_  
Telephone/Fax numbers: \_\_\_\_\_

We have examined and have no reservations for this Supply of Goods.  
We offer to supply in conformity with the delivery schedule as per office Requirements

Official Stamp

प्रमुख कार्यकारी अधिकृत

